

# Blower Door Pre-Testing Requirements

*Please ensure the following checklist is complete prior to scheduling your Blower Door Test:*

## Home Conditions

### 1. Utilities

- Electricity on
- Water on (Note: run water to fill P-traps)

### 2. Building components & systems

- Door casings, door/window hardware, and weather stripping installed and sealed
- A/C and ductwork installed and functioning properly
- No openings in conditioned space. Seal gaps as necessary.
- Attic accesses fitted and installed
- Attic insulation installed
- Kitchen exhaust hood installed
- Bathroom exhaust fans, toilets, sinks, and showers installed

### 3. Finishing details

- No wet paint on doors/door jambs
- Light fixtures and alarms installed and functioning properly
- All outlets covers installed
- Fuzzy strips in sliding glass doors installed

## Contractors

Please provide the following are required items to obtain a Certificate of Occupancy:

### 1. Completed R405 form

- Address of testing location
- Permit number
- Energy calculation (Manual J/N & S)

## Safety

Please notify E-Calcs Plus, Inc. prior to scheduling if any of the following items have been installed, as different testing procedures are required:

- Combustion appliances
- Spray foam attics
- Makeup air

---

### Additional information

- Once checklist requirements are met, scheduling may take 1-3 business days.
- Non-compliance scheduled jobs upon E-Calcs Plus, Inc.'s arrival will incur a standard trip charge.
- Trades should ideally be off-site during testing; if present, they must remain inside or outside for the test duration.
- Inclement weather may affect testing and could require scheduling.
- If the home fails to meet Florida testing guidelines, E-Calcs Plus will assist in identifying the cause for re-test. Additional tests will be scheduled and charged separately.